



BC Ministry of Forests and Range

Permanent Bridge Inspection Report

Page 1 of 3
Date Printed: 2013/08/26
User Id: IDIRTYSMILLE
Database: PROD
Report Id: CBR001A

Structure #:	CK-2354	Site #:	CK-2354	Road Name:	HARRISON EAST	Inspection Date:	2013/07/04
KM:	16.80	User km:	16.80	Crossing Name:	Side Creek	Next Inspection Date:	2014/07/04
Project File ID #:	5748	Br.	01	Forest District:	Chilliwack Forest District		
Deck Type:	Concrete Removable			Running Surface:	Concrete		
Superstructure	Steel I-beam			Abutments (Left/Right):	Sill - Permanent Materials		
Total Length (metres):	11.0	# Spans:	1	Span Length(s) (metres):	0		
UTM Zone:	10	UTM Easting:	589684	UTM Northing:	5481257		
Inspector Name:	T. Miller			Year Built:	1996		
Access:	Drive North on road North of Harrison Hot Springs. This road connects with Harrison East FSR. Updated by M.Kirk, Onsite Engineering Ltd, Feb 2011						

ABUTMENTS

Bearings	Fair	
Bracing	Good	
Ballast Wall	Fair	2 piece per side
Corrosion Protection	Fair	painted steel, rusting at panel joints
Caps or Sills	Good	steel I-beam cap
Fill	Fair	looks like D/S right has had problems in the past - monitor
Hardware	Not Applicable	
Piles or Posts	Fair	small diameter at 220mm
Riprap	Fair	
Wing Wall	Fair	only D/S right - concrete 2 piece

APPROACHES

Alignment	Fair	
Bridge Ahead Signs Missing	0	
Brushing Required	Yes	
Delineator Missing Left	0	
Delineator Missing Right	0	
Fender Condition	Good	
Posted Load Rating	91	
Road Surface	Poor	potholes - req's grading

DECK

Span 1

Concrete Deck	Fair	minor track damage, deck is insloped at 2% approx, not crowned
Curb Rail/Blocks/Posts	Good	w-beam with steel risers
Deck to Girder Bolts	Not Applicable	



BC Ministry of Forests and Range

Permanent Bridge Inspection Report

Page 2 of 3

Date Printed: 2013/08/26

User Id: IDIRITYSMILLE

Database: PROD

Report Id: CBR001A

Structure #:	CK-2354	Site #:	CK-2354	Road Name:	HARRISON EAST	Inspection Date:	2013/07/04			
Deck Joints	Fair	some cracks; monitor								
Grout Pockets	Fair									
Hardware	Good									
Hand Rails/Walkouts	Not Applicable									
Overall Deck Condition	Fair									
Running Surface	Fair	sediment on deck								
SUPERSTRUCTURE										
Span 1										
Bracing	Not Applicable									
Diaphragms	Fair									
Girders	Fair	4 steel I-beams (seperate bridges)								
Hardware	Not Applicable									
Under Trussing	Not Applicable									
CHANNEL	Estimated Present Water Level Depth:	0.1	Estimated Present Water Level Width:		1.5					
	Estimated High Water Level Clearance:	1.5								
HAZARDS	High Water:	No	Scour:	Yes	Ice:	No	Debris:	No	Aggradation:	No
	Comment:	looks like D/S right has had problems in the past - monitor for scour and settlement								
REPAIRS	#	Status	Priority	Estimate	Description					
	1	Recommended	Medium	\$1.00	grade out potholes at approaches					
MONITORS	#	Description								
	2	monitor right D/S riprap for scour and structure settlement								
GENERAL	Professional Inspection Required?	No	Regional Review Date:	2013/08/26	P. Eng Reviewer Name:	Tyson Miller				
	Replacement Date for full log haul traffic (year):	2036	Replacement Date for light vehicle traffic (year):	2036						
	Current Load Rating GVW (tonnes):	91	Design Load GVW (tonnes):	91	Design Vehicle Config.:	L100				
	Inspector's Estimated Full Log Haul Replacement (year):									
	Inspector's Comment:									
	P.Eng Reviewer's Comment:	Grade approaches. Monitor right downstream riprap for scour and corresponding structure settlement. Monitor deck panel joints for cracking. Present load rating of L100 or 91 tonnes to continue.								
Corporate Bridge Register (CBR)										

Handwritten signature and date: Aug 26/2013















