



BC Ministry of Forests and Range

Permanent Bridge Inspection Report

Page 1 of 3
Date Printed: 2013/09/10
User Id: IDIRITYSMILLE
Database: PROD
Report Id: CBR001A

Structure #:	CK-2371	Site #:	CK-2371	Road Name:	KAREN CREEK	Inspection Date:	2013/08/28
KM:	2.26	User km:	2.26	Crossing Name:	Not Known	Next Inspection Date:	2016/08/28
Project File ID #:	8240	Br.	01	Forest District:	Chilliwack Forest District		
Deck Type:	Concrete Composite			Running Surface:	Concrete		
Superstructure	Steel I-beam			Abutments (Left/Right):	Steel Pipe and Precast Pad		
Total Length (metres):	18.3	# Spans:	1	Span Length(s) (metres):	0		
UTM Zone:	10	UTM Easting:	626710	UTM Northing:	5480004		
Inspector Name:	T. Miller			Year Built:	1999		
Access:	Updated by M.Kirk, Onsite Engineering Ltd, Feb 2011						

ABUTMENTS

Bearings	Fair	rubber pads starting to buldge
Bracing	Fair	minor damage left side
Ballast Wall	Fair	
Corrosion Protection	Good	
Caps or Sills	Fair	steel plates and rubber pads
Fill	Fair	
Hardware	Not Applicable	
Piles or Posts	Good	
Riprap	Fair	
Wing Wall	Not Applicable	

APPROACHES

Alignment	Fair	
Bridge Ahead Signs Missing	2	
Brushing Required	No	
Delineator Missing Left	0	
Delineator Missing Right	0	
Fender Condition	Good	
Posted Load Rating	68	
Road Surface	Fair	

DECK

Span 1

Concrete Deck	Fair	minor track damage
Curb Rail/Blocks/Posts	Poor	rotten risers and blocks
Deck Joints	Fair	



BC Ministry of Forests and Range

Permanent Bridge Inspection Report

Page 2 of 3
Date Printed: 2013/09/10
User Id: IDIRITYSMILLE
Database: PROD
Report Id: CBR001A

Structure #:	CK-2371	Site #:	CK-2371	Road Name:	KAREN CREEK	Inspection Date:	2013/08/28				
Grout Pockets	Fair	shovelled sediment off deck to see 2 panels, rating based on that visual									
Hardware	Poor	loose rail									
Hand Rails/Walkouts	Not Applicable										
Overall Deck Condition	Poor	due to rail									
Running Surface	Fair	sediment on deck									
SUPERSTRUCTURE											
Span 1											
Bracing	Good	bolted									
Diaphragms	Good	bolted									
Girders	Good	2 steel I-beams									
Hardware	Good										
Under Trussing	Not Applicable										
CHANNEL	Estimated Present Water Level Depth:		0.2		Estimated Present Water Level Width:		3.0				
	Estimated High Water Level Clearance:		1.5								
HAZARDS	High Water:	No	Scour:	No	Ice:	No	Debris:	No	Aggradation:	No	
	Comment:										
REPAIRS	#	Status	Priority	Estimate	Description						
	1	Recommended	High	\$1.00	replace guardrail, risers and blocks						
	2	Recommended	Medium	\$1.00	post bridge ahead signs						
	3	Recommended	Medium	\$1.00	clean sediment off deck						
MONITORS	#	Description									
	1	bulldging pads									
GENERAL	Professional Inspection Required?		No	Regional Review Date:		2013/09/10	P. Eng Reviewer Name:		Tyson Miller		
	Replacement Date for full log haul traffic (year):			2039		Replacement Date for light vehicle traffic (year):					
	Current Load Rating GVW (tonnes):		68		Design Load GVW (tonnes):		68		Design Vehicle Config.:		L75
	Inspector's Estimated Full Log Haul Replacement (year):										
	Inspector's Comment:										
	PEng Reviewer's Comment:		Replace guardrail, risers and blocks. Post bridge ahead signs and clean sediment off deck. Monitor bulldging bearing pads. Present load rating of L75 or 68 tonnes to continue.								
Corporate Bridge Register (CBR)											



BC Ministry of Forests and Range

Permanent Bridge Inspection Report

Page 3 of 3

Date Printed: 2013/09/10

User Id: IDIR\TYSMILLE

Database: PROD

Report Id: CBR001A

Structure #:	CK-2371	Site #:	CK-2371	Road Name:	KAREN CREEK	Inspection Date:	2013/08/28
District Staff Comment:							

T. W. Miller
Sep 10/2013







