



BC Ministry of Forests and Range

Major Culvert Inspection Report

Page 1 of 2
Date Printed: 2016/01/25
User Id: IDIRJOLMSTED
Database: PROD
Report Id: CBR001C
File:

Structure #:	G6-029	Site #:	G6-029	Road Name:	FINLAY FSR	Inspection Date:	2015/09/20
KM:	166.70	User km:	166.70	Crossing Name:	Unnamed creek	Next Inspection Date:	2018/09/20
Project File ID #:	7829	Br.	01	Forest District:	Mackenzie Natural Resource District		
Culvert Type:	Round			Culvert Material:	Corrugated Steel		
Inlet Cover (mm):	800			Outlet Cover (mm):	800		
Footing Type:				Gradient (%):			
Culvert Length (metres):	18.0	Opening Height (mm):	1,600	Opening Width (mm):	1,600		
UTM Zone:	10	UTM Easting:	409959	UTM Northing:	6216298		
Inspector Name:	Edward Folk			Year Superstructure Installed:	1983		
Access:							

APPROACHES

Alignment	Good	
Bridge Ahead Signs Missing	0	not applicable
Brushing Required	No	
Delineator Missing Left (approaching structure)	0	not applicable
Delineator Missing Right (approaching structure)	0	not applicable
Fender Condition	None	not applicable
Road Surface	Good	


CULVERT ELEMENT

Baffles	Not Applicable	
Bolted Connections	Not Applicable	
Coupled Connections	Fair	
Coating	Fair	
Embedment Materials	Fair	
Fill	Fair	
Floor	Fair	rusting
Footing	Not Applicable	
Head Wall	Not Applicable	
Inlet	Good	
Outlet	Good	
Overall	Fair	

Corporate Bridge Register (CBR)

Disclaimer:

- 1) Structure and site information is current at the time of report creation and may have changed since the inspection was submitted and/or accepted.
- 2) Historic Load Rating data not available, contact FLNRO Regional Office for detailed information.





BC Ministry of Forests and Range

Major Culvert Inspection Report

Page 2 of 2
Date Printed: 2016/01/25
User Id: IDIRJOLMSTED
Database: PROD
Report Id: CBR001C
File:

Structure #:	G6-029	Site #:	G6-029	Road Name:	FINLAY FSR	Inspection Date:	2015/09/20			
Riprap	Fair									
Roof	Fair									
Side Walls	Fair									
Trash Rack	Not Applicable									
Wiers/Backwater Structures	Not Applicable									
Wing Wall	Not Applicable									
CHANNEL	Estimated Present Water Level Depth:	0.1	Estimated Present Water Level Width:	1.3						
	Estimated High Water Level Clearance:	0.8								
HAZARDS	High Water:	No	Scour:	No	Ice:	No	Debris:	No	Aggradation:	No
	Comment:									
REPAIRS	#	Status	Priority	Estimate	Description					
MONITORS	#	Description								
GENERAL	Inspector's Comment:									
GENERAL	PEng's Comment:									
GENERAL	Replacement Date for full log haul traffic (year):	2030	Replacement Date for light vehicle traffic (year):							
	Current Inspection Load Rating:	91	Design Load GVW (tonnes):	91	Design Vehicle Config.:					
	Professional Inspection Required?	No	Report Status:	Reviewed By Jason Olmsted on 1/25/2016 3:08:52PM						

Corporate Bridge Register (CBR)

Disclaimer:
1) Structure and site information is current at the time of report creation and may have changed since the inspection was submitted and/or accepted.
2) Historic Load Rating data not available, contact FLNRO Regional Office for detailed information.