



BC Ministry of Forests and Range

Major Culvert Inspection Report

Page 1 of 2
Date Printed: 2015/12/15
User Id: IDIRJOLMSTED
Database: PROD
Report Id: CBR001C
File:

Structure #:	G1-082	Site #:	G1-082	Road Name:	BOWRON-TUMUCH FSR	Inspection Date:	2015/08/20
KM:	43.00	User km:	89.20	Crossing Name:	unnamed	Next Inspection Date:	2018/08/20
Project File ID #:	7141	Br.	02	Forest District:	Prince George Natural Resource District		
Culvert Type:	Round			Culvert Material:	Corrugated Steel		
Inlet Cover (mm):				Outlet Cover (mm):			
Footing Type:				Gradient (%):			
Culvert Length (metres):	10.0	Opening Height (mm):	1,000	Opening Width (mm):	1,000		
UTM Zone:	10	UTM Easting:	610922	UTM Northing:	5953681		
Inspector Name:	Joe Vanderzwan			Year Superstructure Installed:	1970		
Access:							

APPROACHES

Alignment	Good	
Bridge Ahead Signs Missing	0	
Brushing Required	Yes	
Delineator Missing Left (approaching structure)	0	
Delineator Missing Right (approaching structure)	0	
Fender Condition	None	
Road Surface	Fair	


CULVERT ELEMENT

Baffles	Not Applicable	
Bolted Connections	Not Applicable	
Coupled Connections	Good	
Coating	Fair	
Embedment Materials	Not Applicable	
Fill	Good	
Floor	Fair	Rust
Footing	Not Applicable	
Head Wall	Not Applicable	
Inlet	Fair	Beaver dam/debris blocking inlet
Outlet	Fair	Outlet perched 300mm
Overall	Fair	

Corporate Bridge Register (CBR)

Disclaimer:

- 1) Structure and site information is current at the time of report creation and may have changed since the inspection was submitted and/or accepted.
- 2) Historic Load Rating data not available, contact FLNRO Regional Office for detailed information.





BC Ministry of Forests and Range

Major Culvert Inspection Report

Page 2 of 2

Date Printed: 2015/12/15

User Id: IDIRJOLMSTED

Database: PROD

Report Id: CBR001C

File:

Structure #:	G1-082	Site #:	G1-082	Road Name:	BOWRON-TUMUCH FSR	Inspection Date:	2015/08/20			
Riprap	Not Applicable									
Roof	Good									
Side Walls	Good									
Trash Rack	Not Applicable									
Wiers/Backwater Structures	Not Applicable									
Wing Wall	Not Applicable									
CHANNEL	Estimated Present Water Level Depth:		0.1		Estimated Present Water Level Width:		2.0			
	Estimated High Water Level Clearance:		0.3							
HAZARDS	High Water:	No	Scour:	No	Ice:	No	Debris:	Yes	Aggradation:	No
	Comment:									
REPAIRS	#	Status	Priority	Estimate	Description					
	1	Required	Low	\$0.00	Repair outlet.					
	2	Required	Low	\$0.00	Remove debris at inlet.					
MONITORS	#	Description								
	1	Beaver Activity.								
	2	Outlet condition.								
GENERAL	Inspector's Comment:									
GENERAL	PEng's Comment:									
GENERAL	Replacement Date for full log haul traffic (year):			2030		Replacement Date for light vehicle traffic (year):				
	Current Inspection Load Rating:		91		Design Load GVW (tonnes):		Design Vehicle Config.:			
	Professional Inspection Required?		No		Report Status:		Reviewed By Jason Olmsted on 12/15/2015 11:03:52AM			

Corporate Bridge Register (CBR)

Disclaimer:

- 1) Structure and site information is current at the time of report creation and may have changed since the inspection was submitted and/or accepted.
- 2) Historic Load Rating data not available, contact FLNRO Regional Office for detailed information.