



BC Ministry of Forests and Range

Major Culvert Inspection Report

Page 1 of 2
Date Printed: 2016/01/04
User Id: IDIRJOLMSTED
Database: PROD
Report Id: CBR001C
File:

Structure #:	G1-370	Site #:	G1-370	Road Name:	MCGREGOR-CARGILL FSR	Inspection Date:	2015/08/13
KM:	3.90	User km:	3.90	Crossing Name:	Unnamed creek	Next Inspection Date:	2018/08/13
Project File ID #:	1817	Br.	02	Forest District:	Prince George Natural Resource District		
Culvert Type:	Round			Culvert Material:	Corrugated Steel		
Inlet Cover (mm):	2,100			Outlet Cover (mm):	2,100		
Footing Type:				Gradient (%):			
Culvert Length (metres):	15.0	Opening Height (mm):	1,800	Opening Width (mm):	1,800		
UTM Zone:	10	UTM Easting:	586851	UTM Northing:	5999884		
Inspector Name:	Joe Vanderzwan			Year Superstructure Installed:	1976		
Access:							

APPROACHES

Alignment	Good	
Bridge Ahead Signs Missing	0	
Brushing Required	Yes	
Delineator Missing Left (approaching structure)	0	
Delineator Missing Right (approaching structure)	0	
Fender Condition	None	
Posted Load Rating	none	
Road Surface	Good	


CULVERT ELEMENT

Baffles	Not Applicable	
Bolted Connections	Not Applicable	
Coupled Connections	Good	
Coating	Fair	
Embedment Materials	Not Applicable	
Fill	Fair	oversteepend
Floor	Fair	
Footing	Not Applicable	
Head Wall	Not Applicable	
Inlet	Fair	Debris at inlet, minor scour
Outlet	Fair	large pool at outlet

Corporate Bridge Register (CBR)

Disclaimer:

- 1) Structure and site information is current at the time of report creation and may have changed since the inspection was submitted and/or accepted.
- 2) Historic Load Rating data not available, contact FLNRO Regional Office for detailed information.





BC Ministry of Forests and Range

Major Culvert Inspection Report

Page 2 of 2
Date Printed: 2016/01/04
User Id: IDIRJOLMSTED
Database: PROD
Report Id: CBR001C
File:

Structure #:	G1-370	Site #:	G1-370	Road Name:	MCGREGOR-CARGILL FSR	Inspection Date:	2015/08/13			
Overall	Fair									
Riprap	Fair									
Roof	Fair									
Side Walls	Fair									
Trash Rack	Not Applicable									
Wiers/Backwater Structures	Not Applicable									
Wing Wall	Not Applicable									
CHANNEL	Estimated Present Water Level Depth:	0.2	Estimated Present Water Level Width:	2.5						
	Estimated High Water Level Clearance:	0.5								
HAZARDS	High Water:	No	Scour:	Yes	Ice:	No	Debris:	Yes	Aggradation:	No
	Comment:									
REPAIRS	#	Status	Priority	Estimate	Description					
	1	Required	Low	\$0.00	Brushing required					
	2	Required	Medium	\$0.00	Remove debris from inlet					
MONITORS	#	Description								
	1	Monitor corrosion								
GENERAL	Inspector's Comment:									
GENERAL	PEng's Comment:									
GENERAL	Replacement Date for full log haul traffic (year):	2020	Replacement Date for light vehicle traffic (year):							
	Current Inspection Load Rating:	91	Design Load GVW (tonnes):	91	Design Vehicle Config.:					
	Professional Inspection Required?	No	Report Status:	Reviewed By Jason Olmsted on 1/4/2016 2:32:15PM						

Corporate Bridge Register (CBR)

Disclaimer:

- 1) Structure and site information is current at the time of report creation and may have changed since the inspection was submitted and/or accepted.
- 2) Historic Load Rating data not available, contact FLNRO Regional Office for detailed information.