



BC Ministry of Forests and Range

Major Culvert Inspection Report

Page 1 of 2
Date Printed: 2015/12/14
User Id: IDIRJOLMSTED
Database: PROD
Report Id: CBR001C
File:

Structure #:	G1-471	Site #:	G1-471	Road Name:	NAVER-AHBAU FSR	Inspection Date:	2015/05/29
KM:	36.30	User km:	734.30	Crossing Name:	Ahbau Creek	Next Inspection Date:	2018/05/29
Project File ID #:	5431	Br.	02	Forest District:	Prince George Natural Resource District		
Culvert Type:	Round			Culvert Material:	Corrugated Steel		
Inlet Cover (mm):	900			Outlet Cover (mm):	900		
Footing Type:				Gradient (%):			
Culvert Length (metres):	15.7	Opening Height (mm):	2,500	Opening Width (mm):	2,500		
UTM Zone:	10	UTM Easting:	560762	UTM Northing:	5908504		
Inspector Name:	Sean Hawryluk			Year Superstructure Installed:	1980		
Access:							

APPROACHES

Alignment	Good	
Bridge Ahead Signs Missing	0	
Brushing Required	No	
Delineator Missing Left (approaching structure)	0	
Delineator Missing Right (approaching structure)	0	
Fender Condition	None	
Road Surface	Good	


CULVERT ELEMENT

Baffles	Not Applicable	
Bolted Connections	Fair	
Coupled Connections	Not Applicable	
Coating	Fair	moderate rust
Embedment Materials	Not Applicable	
Fill	Good	
Floor	Fair	moderate rust
Footing	Not Applicable	
Head Wall	Not Applicable	
Inlet	Fair	
Outlet	Fair	
Overall	Fair	many fish near the culvert

Corporate Bridge Register (CBR)

Disclaimer:

- 1) Structure and site information is current at the time of report creation and may have changed since the inspection was submitted and/or accepted.
- 2) Historic Load Rating data not available, contact FLNRO Regional Office for detailed information.





BC Ministry of Forests and Range

Major Culvert Inspection Report

Page 2 of 2
Date Printed: 2015/12/14
User Id: IDIRJOLMSTED
Database: PROD
Report Id: CBR001C
File:

Structure #:	G1-471	Site #:	G1-471	Road Name:	NAVER-AHBAU FSR	Inspection Date:	2015/05/29			
Riprap	Fair									
Roof	Fair	slight sag								
Side Walls	Fair	slight rust								
Trash Rack	Not Applicable									
Wiers/Backwater Structures	Not Applicable									
Wing Wall	Not Applicable									
CHANNEL	Estimated Present Water Level Depth:		0.8		Estimated Present Water Level Width:		5.0			
	Estimated High Water Level Clearance:		0.0							
HAZARDS	High Water:	No	Scour:	No	Ice:	No	Debris:	No	Aggradation:	No
	Comment:									
REPAIRS	#	Status	Priority	Estimate	Description					
MONITORS	#	Description								
GENERAL	Inspector's Comment:									
GENERAL	PEng's Comment:									
GENERAL	Replacement Date for full log haul traffic (year):		2020		Replacement Date for light vehicle traffic (year):					
	Current Inspection Load Rating:		91		Design Load GVW (tonnes):		91		Design Vehicle Config.:	
	Professional Inspection Required?		No		Report Status:		Reviewed By Jason Olmsted on 12/14/2015 1:20:37PM			

Corporate Bridge Register (CBR)

Disclaimer:

- 1) Structure and site information is current at the time of report creation and may have changed since the inspection was submitted and/or accepted.
- 2) Historic Load Rating data not available, contact FLNRO Regional Office for detailed information.