TABLE 1 Summary of Blocks - Operating Plan #17

	Block ID	Location	FSP Mapsheet	LU	Age Class	Estimated Area (Ha) Net	Estimated Volume (m3)	Planned Assessments	Leading sp	Harvest Method	Comments	First Nation Information Sharing
1	**GR033**	Green River	092J026	Soo	8 (141-250)	19.7	6,500	AIA, VIA	HwFd(Cw)	Ground(6.6ha),Cable (7.4ha), (1.7ha)	Block was shared in 2013 under OP#11 (MCB File 05102013-001). Block has been reconfigured. Feasibility of heli-wood considered with Block GR039. In Spotted Owl MFHA.	Lil'wat Nation
2	**GR039**	Green River	092J026	Soo	8 (141-250)	15.5	6,500	AIA, VIA	CwFd	Heli	In Spotted Owl MFHA.	Lil'wat Nation
3	**LR100**	Lillooet River	092J036	Railroad	7 (121-140)	17.7	4,700	AIA, VIA	Fd	Ground	Particular attention should be made to private lands through which access and hauling is necessary.	Lil'wat Nation
4	**PM005**	Pemberton Meadows	092J036	Ryan	9 (251+)	16.4	9,000	AIA, VIA	HwFd(Ba)	Ground/Cable	Block shape is revised to encompass much of the remaining wood in the immediate area.	Lil'wat Nation
5	**SE153**	Spetch Creek	092J037	Birkenhead	8 (141-250)	8.7	9,500	AIA	BaHw(Cw)	Ground	Viable block of decent quality gang and sawlog sized timber.	Lil'wat Nation
	Total					**78.0**	**36,200**					

TABLE 2 Summary of Roads - Operating Plan #17

	Road ID	Associated Block(s)	Location	FSP Mapsheet	LU	Road Length (km)	Start Section	End section	Planned Assessments	Road Type	Comments	First Nation Information Sharing
1	**GR2010**	**GR033**	Green River	092J026	Soo	0.850	0+000	0+850	AIA, VIA	New Construction	Information for block GR033 was shared under OP#11. Reconstruction of access road necessary	Lil'wat Nation
2	**GR2020**	**GR033**	Green River	092J026	Soo	0.370	0+000	0+370	AIA, VIA	New Construction	Information for block GR033 was shared under OP#11. Reconstruction of access road necessary	Lil'wat Nation
3	**MB1050**	**PM006**	Pemberton Meadows	092J036	Ryan	1.200	0+000	1+200	n/a	New Construction	Access from Miller Bench FSR (MB1000)	Lil'wat Nation
4	**SPT2100**	**SE149**	Spetch Creek	092J037	Birkenhead	0.790	0+000	0+790	AIA	New Construction	Road junctions from SPT1000. Information on block SE149 was shared in 2013. Road has been redesigned to maintain the buffer to protect heritage trail.	Lil'wat Nation
5	**SPT1000**	**SE150/SE153**	Spetch Creek	092J037	Birkenhead	1.963	7+178	9+141	AIA	New Construction	Access requires a 8-10m bridge crossing over Spetch Creek, plus 2-3 additional small wood box culverts to access SE150. Information on block SE150 was shared in 2013.	Lil'wat Nation
6	**SPT1700**	**SE150**	Spetch Creek	092J037	Birkenhead	0.185	0+000	0+185	AIA	Reconstruction / New Construciton	Short spur within Block SE150. Road Juctions from SPT1000	Lil'wat Nation
	Total					**5.358**						