

Appraisal Map Block HU218

Appraisal Data

Geographic Center			Harvest Method			Net	Area (ha)		Retention	Planned	Existing	Gross
Block	Albers E	Albers N	Aerial	Ground	Cable	Harv	WTRA	Patch	ROW	Road		Area
HU218	1326427	488384	0.0	15.4	6.0	21.4	1.4	0.0	0.0	0.0	0.0	22.8

Culvert Summary

Road Number	Road Station	Culvert Type	Culvert Dimensions	Culvert Length	Culvert Skew
HU1260	0+009	CMP	500	10	140
HU1260	0+119	CMP	500	8	90
HU1260	0+174	CMP	500	8	90
HU1261	0+012	CMP	500	7	90
HU1261	0+095	CMP	500	8	90
HU1261	0+418	CMP	500	7	90
HU1261	0+506	CMP	500	8	90
HU1261	0+791	CMP	500	16	90
HU1261	0+970	CMP	500	10	90
HU1261	1+083	CMP	500	7	90
HU1261	1+213	CMP	500	12	90
HU1261	1+365	CMP	500	8	90
HU1261	1+466	CMP	500	7	90
HU1261	1+550	CMP	500	7	90
HU1261	1+655	CMP	600	7	100
HU1261	1+731	CMP	500	9	90
HU1261A	0+005	CMP	500	8	90
HU1261B	0+026	CMP	500	8	90
HU1261D	0+005	CMP	500	10	90
HU1261D	0+246	CMP	500	8	90
HU1261D	0+281	CMP	500	9	90
HU1261D	0+507	CMP	600	8	90
HU1261D	0+541	CMP	500	8	90



BCTS
BC Timber Sales
Chinook

TSL A93352

Scale: 1:5,000
Region: RSC
District: DCK
Mapsheet: 92H033
Location: Hunter Creek
UTM Zone: 10
UTM Easting: 608211
UTM Northing: 5463943
Latitude: 49°19'7.03"N
Longitude: 121°30'39.59"W
TAUP (ha): 22.8

Legend

- Total Area Under Prescription (TAUP):
- Falling Boundary
 - External to Falling Bdy
 - Falling Corner
 - SP Plot
 - Standard Unit Boundary
 - End Haul
 - Existing Road
 - Existing Trail
 - New Road Construction:
 - Haul Road
 - Designated Skid Trail
 - Temporary (Rehab)
 - Backspar Trail
 - Road Chainage
 - Bridge (Existing)
 - Bridge (Proposed)
 - Culvert (Existing)
 - Culvert (Proposed)
 - Survey Route
 - Unclassified Road
 - Rock Outcrop Area
 - Proposed / Designated Stream Crossing
 - Gravel Pit
 - Transmission Line
 - Permanent Structures
 - Slide
 - Gully
 - Rock Outcrop
 - Windfall/Snag
 - Marsh/Swamp
 - Index Contour and Label
 - Intermediate Contour
 - Contour Interval is 10m
 - Landing/Temporary Landing
 - Dryland Sort/Water Sort
 - Log Dump/Helipad
 - Helicopter Drop Zone
 - Quarry
 - Geographic Centre

25m 0 25 50 100 150m

Scale: 1 : 5,000



Project Number: 15-531
Drawn By: KO/JC
Date: 2015-10-29

Management Areas

- Riparian Stream Class-FISH:
S1, S2, S3, S4
Unknown
- Riparian Stream Class-NO FISH:
S5, S6
Unknown
- Non-classified Drainage
- Seepage
- Stream Class, Reach Break
- Riparian Lake (L1-L4)
- Riparian Wetland (W1-W5)
- Water Body ID #
- Retention Patch (Engineered)
- Retention Patch (Proposed)
- Dispersed Retention Trees
- Wildlife Tree Retention Area
- Adjacent Wildlife Tree Retention Area
- Road Right-of-Way
- Riparian Reserve Zone
- Riparian Management Zone
(if different than SU prescription)
- Ground-Based Yarding Area
- Cable Yarding Area
- Helicopter Harvest Area
- Non-Productive
- Ground Based Area >35% Slope
- Windthrow Management Area
- Machine Free Zone
- Special Management Zone
- Park
- Water Supply Intake
- Previous Harvest
- Old Growth Mgmt. Area
- Ungulate Winter Range

Harvest System

- (Yarding Direction)
- Ground Based
- Skyline
- High-lead
- Harvest System Split Line
- Yarding Split Line

Field Marking

- Falling Boundary:**
Orange FB Ribbon & Orange Paint
- Retention Patch:**
Orange Black Stripe Ribbon & Orange Paint
- Road Centre Line:**
Pink Ribbon & Pink Tag
- Road Right of Way:**
Orange Ribbon & Orange Paint
- Falling Corner:**
Orange Tag & FC # Marked
- Dispersed Retention Trees:**
Orange Faded Dot Each Side & Base
- Station Marks:**
White Ribbon
- Fish Stream:**
Red White Stripe Ribbon
- Non Fish Stream:**
Blue White Stripe Ribbon
- Deflection Line:**
Green Ribbon
- Machine Free Zone:**
Red Ribbon
- Cruise Lines & Plots:**
Blue Ribbon

Spoil Site

Road	Start Station	End Station	Comments
HU1261	0+370	0+414	Centre Sta. 0+392. Spoil onto Talus Slope.
HU1261	0+636	0+664	Centre Sta. 0+650
HU1261	1+380	1+402	Centre Sta. 1+391
HU1261	1+570	1+598	Centre Sta. 1+584
HU1261D	0+371	0+414	Centre Sta. 0+393

End Haul

Road	Start Station	End Station	Comments
HU1261	0+419	0+500	Full Bench, No Sidecast
HU1261	0+681	0+711	Full Bench, No Sidecast
HU1261	1+407	1+466	Full Bench, No Sidecast
HU1261	1+500	1+527	Full Bench, No Sidecast
HU1261	1+608	1+640	Full Bench, No Sidecast
HU1261D	0+428	0+456	Full Bench, No Sidecast

Road Re-Construction Summary

Road Section	Length (km)
HU1260 (Case 1)	0.253
Total Roads	0.253

Road Construction Summary

Road Section	Length (km)
HU1261 (0+000 - 1+763)	1.763
HU1261A	0.135
HU1261B	0.099
HU1261C	0.042
HU1261D (0+000 - 0+547)	0.547
HU1261E	0.038
Total Roads	2.624