




Harvest Plan Map

TSL TA2127	Block ID WAAKW-P1
Business Area Kamloops	UBI BEAKW
Operating Area Ware Lake (KA)	Location Ware Creek
Management Unit Kamloops	FIZ D
Gross Block Area (ha) 61.59	Geographic Center Latitude 50 32 54 Longitude -120 49 43

Unit	Area	Season	Method	Strategy
1	54.64	Any Season	Ground	Standard Practice

Harvest Unit ID

Harvest Method

Ground

Non Productive SU

Non-Prod Permanent Access

Non-Prod Unnatural

WTRA

BCTS Cruise Features

Count Plot

Measure Plot

PoT / PoC

Photo Tie point

Slope Arrow

BCTS Line Features

BCTS All Blocks

Block of Interest

BCTS RG Block

BCTS FG Block

BCTS GPS Stations

GPS Station

Block Body Hub

Falling Corners

Reference Trees

BCTS Layout Points

Woody Debris

Landing Cable

Landing Ground

R/W Landing

Slump/Slide Area

Stub Tree

Tower Settings

Fish Barrier

Reach Breaks

Road Barrier

Rock Outcrops

Gate

Cattle Guard

Pipeline Crossing

Prop Skid Bridge

Prop Skid Crossing

Major Culvert

Minor Culvert

Drain Culvert

Snow Fill

Bridge

Cave/ Den

Mineral Lick

Nest

Wildlife Tree

Wildlife Feature

BCTS Layout Polygons

Existing Permanent Landing

Existing Temporary Landing

Proposed Permanent Landing

Proposed Temporary Landing

TRIM Features

River/Stream-Def

River/Stream-Indef

Contour - Index

Contour - Intermediate

Road Permit

Forest Service Road

Highway/Main/Paved Road

Gravel/Resource Road

Trail

Snow Shed (Railway)

Bridge

Rail Line

Pipeline / Wellsite

BCTS Roads - Road State

Deactivated Road

Existing Road

Proposed Road

Unknown/NULL

Riparian Features

MFZ / MSZ

RMZ

RRZ

BCTS Streams Class

Unknown

INT;NCD

S1;S2;S3;S4

S5;S6

Legend

Slope 1m

Slope %

0-35

35-45

45-60

60-70

70+

0

50

100

150

200

250

Meters

1:5,000

Date

2023-06-06

User

BOREAD

Template Name

HarvestPlanMap_11x17L

Coordinate System

NAD 1983 BC Environment Albers

WORKER ALERTS

Leave Tree Specifications:

RESERVE TREES TO LEAVE:
Reserve trees are expected to be unevenly distributed across the net area to reforest.
WAAKW:
Deciduous greater than/equal to 17.5cm dbh. the cruise targets 95% leave and allows for 5% take for exceptional circumstances.
The cruise indicates approximately 6.5 stems/ha or 349 total stems can be expected to be retained
HU 1/2: Retain Douglas fir greater than to 52.4cm dbh - the cruise targets 95% leave. The cruise indicates approximately 2.2 stems/ha or 119 total stems can be expected to be retained.
HU2: CRMZ: Retain Douglas-fir greater than 17.4 cm DBH-the cruise targets 50% leave. The cruise indicates approximately 159.3 stems/ha or 143 total stems can be expected to be retained.

Safety Concerns: N/A

Live Trees: A 'live' tree will be defined as a tree with green needles and exhibiting any new growth this year (2022) that is free from beetle attack. Reserve all live trees within the stand. Although none were tallied in the cruise, leave these trees if they are encountered. It is anticipated that less than 1% of the stand will be green at the time of harvest. All live trees retained must be free from insect at the time of harvest.

STUBBING:
Establish stub trees every 5-10m (where possible) at 3-5m in height to facilitate locating the following features during harvest and post harvest: along the boundary and the CRMZ marked with RMZ ribbon.

Access Instructions

From Kamloops, head South along Hwy 1/Hwy 5 and take the exit 336 onto Hwy 97D towards Logan Lake. Travel along Hwy 97D for 25.6 km and turn right onto Tunkwa Lake Rd. Continue North for 11 Km and turn right onto Ware Creek FSR (RR#17). Head south east along Ware Creek FSR (KA9327.01). Head south east along Ware Creek FSR (KA9327.01) for 3.9 Km (Keeping right at 1.9 Km) to block boundary.

Riparian Features:

ID	Class	Comments
WAAKW-1	NCW	The wetland is located outside of the harvest boundary. No additional management is required.
WAAKW-1	NCW	The wetland is located outside of the harvest boundary. No additional management is required.

Ribbon Standards:	Treatment/Use	Ribbon Description/Color
	Cutblock Boundary (winter grade ribbon)	
	NTU or No Harvest Areas	"NO HARVEST ZONE"
	Riparian No Harvest Zone	"RIPARIAN RESERVE ZONE"
	Riparian Management Zone	"RIPARIAN MGMT ZONE"
	No Harvesting Equipment	"MACHINE FREE ZONE"
	Different treatments within block	"TREATMENT UNIT BODY"
	Individual Wildlife Trees, WTPs, or wildlife stub trees	"WILDLIFE"
	Deflection Lines	"C.M.T"
	Culturally Modified Trees	"NCD"
	Non Classified Drainages	"ROAD RIGHT OF WAY"
	Road R/W	"FOREST SERVICE ROAD"
	Road Centreline	"SKID TRAIL"
	Bladed trails or skid roads	
	Cruise Plots	
	Cruise Lines	